

BEDROCK

GEOTECHNICAL EQUIPMENT

BEDROCK Drilling System

Solar Farm Post Pre-Drilling (DTH) Configured for Vertical Operation



Features

- Fully Radio Remote
- Rotary Head 1650NM
- 100mm Split Rod guide
- Interlocking Spanners
- Laydown Support Legs
- Forklift Compatible

Specifications

- Overall Length 4M
- Stroke 3.2M
- Torque up to 2000NM
- Push-Pull Force 1750kg
- 4" DTH Hammer

Options

- Safety Cage
- Allen Bradley Wireline eStop
- 4 way cradle
- "Y" Axis Slew



Unit 3, City Link Park Forge Hill,
Cork Ireland T12 K446



www.bedrock.ie



00 353 (0)21 7355696
00 353 (0)87 2346060



sales@bedrock.ie